

To All Contractors that are requesting water service,

The Town of Chino Valley Utility Department would like to request that all water service lines are installed in accordance with the following:

When a contractor is installing a meter set and meter box, they shall install a customer shut off valve downstream of the meter (see diagram). This will provide the contractor/customer a point to control the water flow to the property.

Once the meter set, meter box and customer shut off valve has been properly installed, the Utility Department will install a meter. The curb stop will be left on supplying water to the property, the water flow must be controlled by the customer shut off valve. At this point the meter box should not be accessed by contractors or subs. Please keep the lids on the meter boxes and use only the customer shut off valve to control the water.

